

SECTION 01 57 19.01 20 SUPPLEMENTAL TEMPORARY ENVIRONMENTAL CONTROLS

Delete 1.1.1.1.2 Surplus Soils Disposal for Camp Lejeune in its entirety and replace with the following:

“1.1.1.1.2 Surplus Soils Disposal for Camp Lejeune & MCAS New River

Transport all surplus soil to one of the designated locations on government property. No surplus material will leave government property without approval of installation Environmental Program Manager and the Contracting Officer. Deliver and properly manage any surplus soil that cannot be reused on its originating site to one of the following locations:

- a. Area managed by G-3/5 for reuse on training areas for various maintenance activities:

3.5-acre storage, within TLZ Condor off Verona Loop Road, approximate coordinates 34°38'07.3"N 77°26'41.7"W.

Coordinate with G-3/5, Mr. Dave Lynch or Mr. Bill Van Pelt, MCI EAST-MCB CAMLEJ at (910) 451-5772/8799, to determine capacity available at the storage location, prior to delivery.

This site operates Monday through Thursday between 0730 and 1500.

- b. Area managed by PWD for use as daily cover:

Base landfill, located on Piney Green Road, approximate coordinates 34°41'26.9"N 77°19'27.4"W.

Contractor shall provide temporary silt fencing around designated stockpile areas as needed.

Coordinate with landfill POC: Joe Powers at (910) 451-4998.

This site operates Monday through Thursday between 0730 and 1500 and on Friday between 0700 and 1400.

Contact POCs listed above 7 to 10 days in advance to coordinate delivery of material at the storage locations.

Prior to transportation to one of the designated locations, screen all surplus soil to remove all objects greater than 3 inches and deleterious material. Deleterious material consists of organic debris such as roots, stumps, timber, and construction debris. Construction debris shall include, but is not limited to wood, plastic, glass, concrete, brick, and metal. Dispose of deleterious material and objects larger than 3 inches in accordance with Section 01 57 19 Temporary Environmental Controls.

Provide all plant, material, and labor for placement and management of the surplus material at the designated locations. Grade surplus material to a flat condition and slope to provide positive drainage daily. Submit the following verification documents to the Contracting Officer for review and approval:

- 1) Photographic documentation that surplus soil has been properly placed. Photograph will include time and date of image.
- 2) Certification statement indicating volume, in cubic yards (CY), of material delivered and confirming material is free of contaminants.

NOTE: Soil contaminated with debris or chemicals cannot be disposed at the stockpile locations. If contaminated soils are suspected or confirmed through presence of UXO, odors, or visual staining, affected soils must be properly tested, manifested, and disposed of in accordance with RCRA regulations. Contact Base EMD, ER Program Manager, for more information.”